BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/20/2017-18, Date: 10.08.2017

Indet No: BBMP/2017-18/OW/WORK_INDENT26740

SCHEDULE -B

Name of Work: Developmental and other works at Sidharthanagara in ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	4147.51	Earthwork in surface excavation in Hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	Cum	252.00	Rupees Two Hundred Fifty Two Only
2	992.79	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications	Cum	324.00	Rupees Three Hundred Twenty Four Only
3	149.31	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement concrete road.	Cum	694.00	Rupees Six Hundred Ninety Four Only
4	365.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work) - 62.5mm nominal OD pipes	mtr	1590.00	Rupees One Thousand Five Hundred Ninety Only
5	4375.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 50mm nominal OD pipes	mtr	515.00	Rupees Five Hundred Fifteen Only
6	30.00	Providing and fixing gun metal wheel valve conforming to IS specification of approved make as per directions including all lead and lift etc., complete.- for 50mm dia	nos	1641.00	Rupees One Thousand Six Hundred Forty One Only
7	1926.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work) - 32mm nominal CD pipes	mtr	246.00	Rupees Two Hundred Forty Six Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

8	3.73	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 7.5Newton per sqmm (Machine moulded Wirecut bricks) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	mtr	11851.00	Rupees Eleven Thousand Eight Hundred Fifty One Only
9	1200.00	Providing and fixing in position Bib Cock of approved quality 25mm nominal bore - NP including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	nos	246.00	Rupees Two Hundred Forty Six Only
10	497.70	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.	Cum	2435.00	Rupees Two Thousand Four Hundred Thirty Five Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner